

FOOTWAY WORKS

150,254.03

15,025.40

165,279.43**Assumptions:**

700m length

1.4m width

Full depth reconstruction, heavy duty at field crossing points

Full extent of footway has concrete subbase so hard dig

50% of kerb foundation will require replacement

Existing chamber construction satisfactory

Sufficient existing kerbs to relay length of site

Subject to satisfactory surveys

Duration: 9 weeks

Employer's Risks:

Existing chamber will require reconstruction prior to resurfacing

Excavation and disposal of tar bound material

Theft of material from site

Insufficient "good" kerbs to relay length of footway

Regulating sub base required for footway construction

Excavation / Filling of soft spots and voids

CARRIAGEWAY RESURFACING

25,396.30

2,539.63

27,935.93**Assumptions:**

700m length

3.0m width

40mm milling, 40mm inlay surface course

Millings to Rights of Way

No corrective patching to existing defective areas

Footway reinstatement completed prior to carriageway resurfacing

Duration: 5 days

Employer's Risks:

Defective sub construction of carriageway

Excavation and disposal of tar bound material

Additional surface course materials required as regulating

PASSING PLACES (4 NO.) CONSTRUCTION

37,671.56

3,767.16

41,438.71**Assumptions:**

Full 2m width is available at each proposed location

Ground Conditions are suitable for proposed mass concrete

Standard highway construction allowed for, no heavy duty (bus route?)

Dimensions of build out as per drawings supplied

225mm dia drainage run suitable within build out construction

Duration: 7 days

Employers Risks:

Ground conditions require stabilisation before construction

Additional drainage required. (Gulleys in passing places, length of culverts

Excavation / Filling of soft spots and voids