

New road markings associated with priority working system

Existing 10m dropped kerb access to remain

Milk House Water bridge. (No. R08-04)



- NOTES:
1. Site extents are approximate and are to be finalised.
 2. Do not scale from this drawing.
 3. All dimensions are in metres unless stated otherwise.




Full footway construction consisting of: AC 6 de base surf 100/150 (20mm thick), AC 20 de base 100/150 (20mm thick) to BS EN 13108-2:2006 sub-base. (Average footway width 1.5m)

Additional works:

- Gully cleaning
- Extensive hedge cutting
- Excavation and removal of additional rock as verge protection in this area!

CAUTION:

- Overhead cables present in area
- BT
- Scottish and Southern Electric (See NRSWA info)



Item	Code	Description	Quantity
A	1021	PRIORITY WORKING	1
B	1022	REDUCED PAV. LENGTH	1
C	1023	ALTERN. WIDTHS	1
D	1024	ORIGINAL	1

DRAFT



PROJECT: 2024 ROAD REVISION
FOOTWAY DATA SCHEME

DRAWING TITLE: PRELIMINARY DESIGN

SCALE: 1:200

DATE: 12/01/2024

REVISION: C