



DANVIC TURF CARE LTD.



Sportsground Contractors

9 Highfield Drive, Longridge, Preston, Lancashire. PR3 3SN
☎01772 780545

Chris Lamb
Trowbridge RFC
Doric Park
Devizes Road
Hilperton BA14 6JB

QUOTATION NO.: 9562
DATE: 8th February 2017

RUNNING TRACK CONSTRUCTION

Dear Mr. Lamb

Thank you very much for contacting us with your enquiry about the construction of a running track at Doric Park, for which I am pleased to supply the following detail and quotation for your consideration:

QUOTATION

Scope of Works

1. Dig out topsoil & subsoil to 150mm deep and deposit in area as directed by Client
2. Erect wooden curbing using timber peg fastenings to form walls of track base
3. Supply and lay Geotech membrane on excavated surface
4. Lay 125mm depth of Scalpings stone and level with camber running to either side
5. Roll to consolidate
6. Add finishing layer - 25mm depth of Red cinder athletic track dressing
7. Roll to firm and retain camber
8. Trim and fill soil around edges of boards and overseed
9. Supply 2 tonnes of Red cinder dressing for maintenance purposes
10. Clear up Contractors Compound and mobilise equipment off site

Track Width options and Costs

OPTION 1:	2.0 metre width x 440 metre length	£ 16,689 + VAT
OPTION 2:	2.5 metre width x 440 metre length	£ 21,054 + VAT
OPTION 3:	3.0 metre width x 440 metre length	£ 24,947 + VAT

Should you have any questions about the construction, please do not hesitate to contact me again.

Once again, thank you for this opportunity.

Richard Sharrock